

EV Plus PDI

To:

Service Manager

You will be receiving your first shipment of EV Plus vehicles soon. Although Pre-Delivery-Inspection will be similar to most Honda vehicles, please be aware of the following:

- Normal tire pressure is 44 psi
- Along with the normal places covered with protective plastic sheet, the PDU cover under the hood and the charging indicator are normally covered. Please remove this protective sheet.
- Some of the vehicles had their 12v battery disconnected for shipment, so the ECU does not "know" the state of charge of the main battery. In fact, the dash display may show "Low Charge" and the battery symbol may be flashing. Also, the climate control will not cool the vehicle. Plug the vehicle into your charging station and let it charge fully. The display will return to normal and the climate control will now function properly.
- The 110v charging cable is not in the vehicle. It will be sent to your dealership as soon as it is available.
- The charge receptacle may be a bit sticky when plugging the charge cable in. It should loosen up after some use.
- Floor mats are now available. Order part number 08P15-S73-170 (H/C 5400197) and bill to American Honda CVA similar to a courtesy delivery.

Let me thank you in advance for your help. I think you will be impressed with the quality of these vehicles.

If you have any questions or problems, do not hesitate to call us for assistance.

**Neil Schmidt
William Powers**

**Auto Engineering
1-800-824-6632**